

UNCLASSIFIED

AD NUMBER	
AD040790	
CLASSIFICATION CHANGES	
TO:	unclassified
FROM:	confidential
LIMITATION CHANGES	
TO: Approved for public release; distribution is unlimited.	
FROM: Distribution authorized to U.S. Gov't. agencies and their contractors; Administrative/Operational Use; JUL 1952. Other requests shall be referred to Naval Proving Ground, Dahlgren, VA.	
AUTHORITY	
USNSWC ltr, 24 Oct 1975; NPG ltr, 9 Jan 1976	

THIS PAGE IS UNCLASSIFIED

THIS REPORT HAS BEEN DELIMITED
AND CLEARED FOR PUBLIC RELEASE
UNDER DOD DIRECTIVE 5200.20 AND
NO RESTRICTIONS ARE IMPOSED UPON
ITS USE AND DISCLOSURE.

DISTRIBUTION STATEMENT A

APPROVED FOR PUBLIC RELEASE;
DISTRIBUTION UNLIMITED.

UNCLASSIFIED

AD_ 40 790

CLASSIFICATION CHANGED
TO: UNCLASSIFIED_
FROM: CONFIDENTIAL_
AUTHORITY:

_____ USNSWC
_____ Notice
24 Oct 75

UNCLASSIFIED

AD NO. ~~40770~~
ASTIA FILE COPY

CONFIDENTIAL
SECURITY INFORMATION

U. S. NAVAL PROVING GROUND
DAHLGREN, VIRGINIA

REPORT NO 1008

WARHEADS FOR AIR TARGET GUIDED MISSILES;
TESTING OF

50th Partial Report

RING WARHEAD NO. 137 WITH PUNCH-FORMED NOTCHES;
FRAGMENTATION TEST OF

FINAL Report

Copy No. 12

Task

Assignment NPG-Re3f-607-1-52

Classification CONFIDENTIAL
SECURITY INFORMATION

CONFIDENTIAL
SECURITY INFORMATION

CONFIDENTIAL

NPG REPORT NO. 1008

U. S. NAVAL PROVING GROUND
DAHLGREN, VIRGINIA

Fiftieth Partial Report

on

Warheads for Air Target Guided Missiles;

Testing of

Final Report

on

Ring Warhead No. 137 with Punch-formed Notches;

Fragmentation Test of

Project No.: NPG-Rc3f-607-1-52
Copy No.: 12
No. of Pages: 7

Date: JUL 28 1952


CONFIDENTIAL
SECURITY INFORMATION

Reproduced

FROM LOW CONTRAST COPY.

REV	DESCRIPTION	DATE	APPROVED

SK 350359



35 RINGS: 33 RINGS AS SHOWN ON NOL/SK 350358
 2 RINGS (ONE AT EITHER END, SAME DIMENSIONS AS
 NOL/SK350358 BUT WITHOUT GROOVES.
 STAGGER NOTCHES OF ADJACENT RINGS.
 UNITE RINGS BY COPPER BRAZING.

REGULATION OF THE CONTROLS OF THIS DRAWING IS THE RESPONSIBILITY OF THE PERSON IN CHARGE OF THE OFFICE OF THE DRAWING		DIVISION OF ORDNANCE, DEPARTMENT OF THE NAVY U. S. NAVAL ORDNANCE LABORATORY WHITE OAK SILVER SPRING 10, MARYLAND		BUOARD DRAWING NO. SK 350359	
		ASSEMBLY TRIAL WARHEAD 137		SCALE 1/2	
APPROVED 18		IT INDICATION OF THE CHIEF OF BUREAU 1		CHECKED DRAWN	
UNLESS OTHERWISE SPECIFIED DIMENSIONS ARE IN INCHES DECIMALS 2 ANGLES 2		DO NOT SCALE THIS DRAWING MATERIAL		SPECIFICATIONS OF LATEST ISSUE APPLY	
NEXT ASSY APPLICATION		USED ON		7-15-32	

NOTICE: THIS DOCUMENT CONTAINS INFORMATION AFFECTING THE NATIONAL DEFENSE OF THE UNITED STATES WITHIN THE MEANING OF THE ESPIONAGE LAWS, TITLE 18, U.S.C., SECTIONS 793 and 794. THE TRANSMISSION OR THE REVELATION OF ITS CONTENTS IN ANY MANNER TO AN UNAUTHORIZED PERSON IS PROHIBITED BY LAW.


CONFIDENTIAL

Fluorobenzene 24.1355

667

1. 67

SK 350358

[illegible]

NOTE. RINGS MAY BE CLOSED BY ARC OR RESISTANCE WELDING.


REVELATION OF THE CONTENTS OF
THIS DRAWING TO AN UNAUTHORIZED
PERSON IS PROHIBITED BY LAW
SEE ESPIONAGE ACT 50 USC 31-32.

BUREAU OF ORDNANCE DEPARTMENT OF THE NAVY						U.S. NAVAL ORDNANCE LABORATORY		SUDDO DRAWING NO.	
						WHITE OAK SILVER SPRING, MD., MARYLAND		SK 350358	
RING									
FOR WARHEAD									JOB ORDER
137									UNIT WT.
SCALE									1/1
APPROVED									19
BY DIRECTION OF THE CHIEF OF BUREAU									
UNLESS OTHERWISE SPECIFIED REMOVE BURRS AND SHARP EDGES. DIMENSIONS ARE IN INCHES. TOLERANCES ON FRACTIONS ± DECIMALS ± ANGLES ±									CHECKED DRAWN
DO NOT SCALE THIS DRAWING									
MATERIAL STEEL									
DAE 212-220									
SPECIFICATIONS OF LATEST ISSUE APPLY									
NEXT ASSY									USED ON
SK 350359									APPLICATION

FRAG NO. 1448

N.P.9 48859

NUL WARHEAD NO. 137



SCALE 1"

NP9-48859


24 MARCH 1952

CONFIDENTIAL

SECURITY INFORMATION

Mass Distribution of Composition C-3 loaded Warhead No. 137.

FIGURE 3



NP9-49072 6

29 APRIL 1952

CONFIDENTIAL

SECURITY INFORMATION

Mass Distribution of Composition C-3 loaded Warhead No. 137-2.

FIGURE 4

0 - 5 1/2	Gms.
	PCS.
620	Gms.

5/8 - 1 1/2	GMS.
222	PCS.
174	GMS.

1 1/2 - 2 1/2	GMS.
77	PCS.
131	GMS.

2 1/2 - 5 GMS.
689 PCS.
2857 GMS.

5-10	GMS
207	PCS
155i	GMS

10-20	GMS
45	PCS
548	GMS

SCALE 1"

NP-49207

7 MAY 1952

~~CONFIDENTIAL~~

SECURITY INFORMATION

Mass Distribution of Composition - loaded Warhead No. 137-3.

Fi

CONFIDENTIAL

NPC REPORT NO. 1008

Ring Warhead No. 137 with Punch-formed Notches;
fragmentation Test of

DISTRIBUTION

Bureau of Ordnance:

Ad3	1
Re2	1
Re3	2
Re3f	5
Chief of Ordnance Department of the Army Attn: ORDTX-AR	2
Navy Research Section Library of Congress Washington 25, D. C. (Via BUORD Re3)	2
Commanding General Aberdeen Proving Ground Aberdeen, Maryland Attn: Technical Information Section Development and Proof Services	1
Commander, Operational Development Force U. S. Atlantic Fleet, U. S. Naval Base Norfolk 11, Virginia	1
Naval Ordnance Laboratory	1
Naval Ordnance Laboratory Attn: Explosives Division	1
Attn: Mr. H. W. Semon	1
Picatinny Arsenal, Dover, N. J. Attn: Technical Division	1
Reports Office APL/JHU, Silver Spring, Maryland	1
APL/JHU, Silver Spring, Md. Attn: Mr. M. S. Norton (Via INSORD, Silver Spring, Md.)	1

CONFIDENTIAL
SECURITY INFORMATION

CONFIDENTIAL

NPG REPORT NO. 1008

Ring Warhead No. 137 with Punch-formed Notches;
Fragmentation Test of

DISTRIBUTION (Continued)

Inst. for Cooperative Research

JHU/1215 St. Paul St.

Via: (District Chief, Phila. Ord District
1500 Chestnut St., Phila. 2, Pa.

Attn: Mr. Edward R. C. Niles)

1

Director, Research and Development Division

New Mexico Institute of Mining and Technology

Socorro, New Mexico

Via: Development Contract Officer

New Mexico Institute of Mining and Technology

Socorro, New Mexico

1

Boeing Airplane Company

Seattle Division

Seattle, Washington

1

Commanding Officer

Frankford Arsenal

Phila. 37, Pa.

1

Local:

OT

1

OTZ

1

OT-1

1

File

1

CONFIDENTIAL

NPG REPORT NO. 1008

Ring Warhead No. 137 with Punch-formed Notches;
Fragmentation Test of

PART A

SYNOPSIS

1. This test was conducted to determine the fragment mass distribution data of 4-5/8" diameter notched ring Warhead No. 137. The notches are formed by utilizing a mechanical punch. This is a cheap and fast method in producing notched rings for controlled fragmentation.

2. a. The punch-formed notches were satisfactory in that all rings fractured at their notches. The copper-brazed bond between rings was too strong, causing some fragments from adjacent rings to remain joined together.

b. Of the three warheads tested, 11 to 35% of the design cubes were in double, triple, and quadruple cube fragments.

CONFIDENTIAL
SECURITY INFORMATION

CONFIDENTIAL

NPG REPORT NO. 1008

Ring Warhead No. 137 with Punch-formed Notches;
Fragmentation Test of

TABLE OF CONTENTS

	<u>Page</u>
SYNOPSIS	1
TABLE OF CONTENTS.	2
AUTHORITY.	3
REFERENCES	3
BACKGROUND	3
OBJECT OF TEST	3
PERIOD OF TEST	3
REPRESENTATIVES PRESENT.	4
DESCRIPTION OF ITEM UNDER TEST	4
PROCEDURE.	5
RESULTS AND DISCUSSION	5
CONCLUSIONS.	6
APPENDIX A - WARHEAD DRAWINGS, PHOTOGRAPHS . .	FIGURES 1-2 (Incl)
APPENDIX B - MASS DISTRIBUTION, PHOTOGRAPHS. .	FIGURES 3-5 (Incl)
APPENDIX C - DISTRIBUTION.	1-2 (Incl)

Ring Warhead No. 137 with Punch-formed Notches;
Fragmentation Test of

PART B

INTRODUCTION

1. AUTHORITY:

This test was authorized by references (a) and (b) and conducted under Task Assignment NPG-Re3f-607-1-52, reference (c).

2. REFERENCES:

- a. NOL Conf Work Request WG/16/52 of 13 March 1952
- b. NOL Conf Work Request WG/20/52 of 18 April 1952
- c. BUORD Conf ltr NF9 Re3f-EJHL:cd b Ser 25777 of 18 September 1952

3. BACKGROUND:

a. Reference (c) authorized the Naval Proving Ground to work directly with the Naval Ordnance Laboratory in the development and testing of guided missile warheads.

b. Three Experimental Warheads Nos. 137, containing 33 notched rings and 2 end rings copper brazed together, 4.625 diameter, and 12.0 long were delivered to the Proving Ground for a fragment mass distribution test. The rings of these warheads were notched by a punch-forming method which is a cheap and fast method.

4. OBJECT OF TEST:

This test was conducted to determine the fragment mass distribution data of 4-5/8" diameter notched ring Warheads Nos. 137. The notches are formed by utilizing a mechanical punch. This is a cheap and fast method in producing notched rings for controlled fragmentation.

5. PERIOD OF TEST:

- | | |
|---|---------------|
| a. Dates Project Letters | 13 March 1952 |
| | 18 April 1952 |
| b. Date All Necessary Material Received | 22 April 1952 |
| c. Date Commenced Test | 24 March 1952 |
| d. Date Test Completed | 7 May 1952 |

Ring Warhead No. 137 with Punch-formed Notches;
Fragmentation Test of

6. REPRESENTATIVES PRESENT:

This test was witnessed in part by Messrs. L. E. Hightower and W. D. Sharp representing the Naval Ordnance Laboratory and Hayes Industries Inc., respectively.

PART C

DETAILS OF TEST

7. DESCRIPTION OF ITEM UNDER TEST:

Three Warheads Nos. 137, 137-2, and 137-3, each 4.625 diameter, 12.00 long, Figure 1, containing 33 rings copper brazed together having internally punch-formed notches, Figure 2, and 2 end rings without notches. All rings were constructed from steel SAE 1010-1020, 4.00 inside diameter, 0.312 wall thickness, 0.345 ring width, notches extended to a 0.156 ± 0.015 depth and were 0.39 apart, maximum width of notches were 0.085. Since the spacing of the punch-formed notches varies slightly, the number of notches per ring is not constant. Most rings had 33 notches, but some had 34. This caused imperfect staggering of the notches of adjacent rings and some places the notches were in line. The warheads were designed to produce approximately 1095 cube shaped fragments weighing 4.6 grams each. Warheads were assembled with only one end plate. All three warheads were loaded with Composition C-3 at the Proving Ground. The weight data are as follows:

<u>Warhead</u> <u>No.</u>	<u>Empty</u> <u>Wt. (lbs.)</u>	<u>Comp. C-3</u> <u>Wt. (lbs.)</u>	<u>Total</u> <u>Wt. (lbs.)</u>
137	13.16	9.33	22.49
137-2	13.61	8.68	22.27
137-3	13.74	8.62	22.36

Ring Warhead No. 137 with Punch-formed Notches;
fragmentation Test of

8. PROCEDURE:

Each warhead was initiated with a Mk 44 auxiliary detonating fuze tetryl pellet (26 grams) and a special engineers blasting cap at the open end of the warhead in a sawdust-filled chamber. After each detonation, the sawdust was sifted and the fragments recovered by the use of sieves and a magnetic separator.

9. RESULTS AND DISCUSSION:

a. The detailed mass distribution data are shown in Figures 3, 4, and 5. The number of fragments in the various weight groups are summarized as follows:

Wt. Group (grams)	No. Fragments		
	#137	#137-2	#137-3
5/8 - 1 1/4	166	194	222
1 1/4 - 2 1/2	94	94	77
2 1/2 - 5	999	784	689
5 - 10	127	170	207
10 - 20	1	31	45
20 - 40	1	0	0

All rings fractured at their notches. The copper braze apparently formed too strong a bond between rings at some locations, causing fragments from adjacent rings to remain together forming double, triple, and quadruple cubes. The number of these are listed as follows:

Warhead No.	Wt. Group (grams)	No. of Fragments			
		Total	Double	Triple	Quadruple
137	5 - 10	127	61	0	0
137-2	5 - 10	170	114	0	0
137-3	5 - 10	207	137	0	0
137	10 - 20	1	0	1	0
137-2	10 - 20	31	2	25	2
137-3	10 - 20	45	11	30	1

The lower number of double and triple cubes obtained on Warhead No. 137 may be attributed to its slightly higher charge-weight ratio, or to a weaker brazing bond.

Ring Warhead No. 137 with Punch-formed Notches;
fragmentation Test of

b. Practically all of the design number of cube fragments were accounted for in the 2 1/2 to 20 grams weight group with the following percentages in the double, triple, and quadruple cube groups:

<u>Warhead No.</u>	<u>% of Design Number</u>		
	<u>Double</u>	<u>Triple</u>	<u>Quadruple</u>
137	11	0.3	0
137-2	21	6.8	0.7
137-3	27	8.2	0.4

PART D

CONCLUSIONS

10. a. The punch-formed notches were satisfactory in that all rings fractured at their notches. The copper-brazed bond between rings was too strong, causing some fragments from adjacent rings to remain joined together.

b. Of the three warheads tested, 11 to 35% of the design cubes were in double, triple, and quadruple cube fragments.

CONFIDENTIAL

NPG REPORT NO.

Ring Warhead No. 137 with Punch-formed Notches;
Fragmentation Test of

The tests upon which this report is based were conducted by:

V. PHILIPCHUK, Fragmentation Battery Officer,
Fragmentation Division
Terminal Ballistics Department

This report was prepared by:

V. PHILIPCHUK, Fragmentation Battery Officer,
Fragmentation Division,
Terminal Ballistics Department

This report was reviewed by:


R. H. LYDDANE, Director of Research,
Terminal Ballistics Department

E. L. LEVSTIK, Lieutenant Commander, USNR,
Terminal Ballistics Batteries Officer,
Terminal Ballistics Department,

W. E. ROBERTSON, Lieutenant Commander, USN,
Terminal Ballistics Officer,
Terminal Ballistics Department,

C. C. BRAMBLE, Director of Research, Ordnance Group

APPROVED: J. F. BYRNE
Captain, USN
Commander, Naval Proving Ground


C. T. MAURO
Captain, USN
Ordnance Officer
By direction

CONFIDENTIAL
SECURITY INFORMATION

UNCLASSIFIED

UNCLASSIFIED